



HAL
open science

BcL-xL Conformational Changes upon Fragment Binding Revealed by NMR

Clémentine Aguirre, Tim Ten Brink, Olivier Walker, Florence Guillière, D. Davesne, Isabelle Krimm

► **To cite this version:**

Clémentine Aguirre, Tim Ten Brink, Olivier Walker, Florence Guillière, D. Davesne, et al.. BcL-xL Conformational Changes upon Fragment Binding Revealed by NMR. PLoS ONE, 2013, 8, pp.e64400. 10.1371/journal.pone.0064400 . in2p3-00839023

HAL Id: in2p3-00839023

<https://in2p3.hal.science/in2p3-00839023v1>

Submitted on 27 Jun 2013

HAL is a multi-disciplinary open access archive for the deposit and dissemination of scientific research documents, whether they are published or not. The documents may come from teaching and research institutions in France or abroad, or from public or private research centers.

L'archive ouverte pluridisciplinaire **HAL**, est destinée au dépôt et à la diffusion de documents scientifiques de niveau recherche, publiés ou non, émanant des établissements d'enseignement et de recherche français ou étrangers, des laboratoires publics ou privés.

Bcl-xL Conformational Changes upon Fragment Binding Revealed by NMR

Clémentine Aguirre¹, Tim ten Brink¹, Olivier Walker¹, Florence Guillière¹, Dany Davesne², Isabelle Krimm^{1*}

¹ UMR5280/Université de Lyon/Université Lyon 1, Institut des Sciences Analytiques, Villeurbanne, France, ² UMR5822/IN2P3/F-69622 Lyon, Université de Lyon, IPNL, Villeurbanne, France

Abstract

Protein-protein interactions represent difficult but increasingly important targets for the design of therapeutic compounds able to interfere with biological processes. Recently, fragment-based strategies have been proposed as attractive approaches for the elaboration of protein-protein surface inhibitors from fragment-like molecules. One major challenge in targeting protein-protein interactions is related to the structural adaptation of the protein surface upon molecular recognition. Methods capable of identifying subtle conformational changes of proteins upon fragment binding are therefore required at the early steps of the drug design process. In this report we present a fast NMR method able to probe subtle conformational changes upon fragment binding. The approach relies on the comparison of experimental fragment-induced Chemical Shift Perturbation (CSP) of amine protons to CSP simulated for a set of docked fragment poses, considering the ring-current effect from fragment binding. We illustrate the method by the retrospective analysis of the complex between the anti-apoptotic Bcl-xL protein and the fragment 4'-fluoro-[1,1'-biphenyl]-4-carboxylic acid that was previously shown to bind one of the Bcl-xL hot spots. The CSP-based approach shows that the protein undergoes a subtle conformational rearrangement upon interaction, for residues located in helices α_2 , α_3 and the very beginning of α_5 . Our observations are corroborated by residual dipolar coupling measurements performed on the free and fragment-bound forms of the Bcl-xL protein. These NMR-based results are in total agreement with previous molecular dynamic calculations that evidenced a high flexibility of Bcl-xL around the binding site. Here we show that CSP of protein amine protons are useful and reliable structural probes. Therefore, we propose to use CSP simulation to assess protein conformational changes upon ligand binding in the fragment-based drug design approach.

Citation: Aguirre C, ten Brink T, Walker O, Guillière F, Davesne D, et al. (2013) Bcl-xL Conformational Changes upon Fragment Binding Revealed by NMR. PLoS ONE 8(5): e64400. doi:10.1371/journal.pone.0064400

Editor: Eugene A. Permyakov, Russian Academy of Sciences, Institute for Biological Instrumentation, Russian Federation

Received: March 11, 2013; **Accepted:** April 12, 2013; **Published:** May 23, 2013

Copyright: © 2013 Aguirre et al. This is an open-access article distributed under the terms of the Creative Commons Attribution License, which permits unrestricted use, distribution, and reproduction in any medium, provided the original author and source are credited.

Funding: The work presented here was supported by the Agence National de la Recherche, project ANR-11-JS07-0008. The funders had no role in study design, data collection and analysis, decision to publish, or preparation of the manuscript.

Competing Interests: The authors have declared that no competing interests exist.

* E-mail: isabelle.krimm@univ-lyon1.fr

Introduction

Protein-Protein Interactions (PPI) play a major role in a large diversity of processes in cells [1]. PPI represent consequently highly attractive targets for the elaboration of chemical probes in chemical biology. PPI are also important therapeutic targets for the design of inhibitors capable of preventing the formation of protein-protein complexes and interfering with biological pathways. However, tackling PPI remains a particularly challenging task in drug design due to the properties of PPI surfaces, by comparison with more typical binding sites of proteins. Protein-protein interfaces happen to be rather flat and large and are therefore less prone to interact with ligands than smaller and deeper pockets found in binding sites of proteins such as enzymes [2–6]. A novel approach in drug design called Fragment-Based Drug Design (FBDD) seems to be a very promising methodology and could help developing PPI inhibitors [2,7,8]. FBDD consists of screening fragment-like molecules against protein targets, using biophysical methods such as Surface Plasmon Resonance, Nuclear Magnetic Resonance and X-ray crystallography [9,10]. Fragments are small, simple and very low molecular weight compounds

(MW < 300 Da) that usually bind proteins with low affinity ($\mu\text{M} < K_D < \text{mM}$). Fragments nevertheless bind proteins through high-quality interactions and display high ligand efficiencies [11,12]. Potent compounds with improved activities ($K_I \approx \text{nM}$) are derived from fragment hits by growing, merging or linking methods [9,13]. PPI inhibitors resulting from fragment-based approaches have been reported for the Bcl-2 family [14–18], for interleukins [19], and for the ZipA/FtsZ interaction [20]. Very recently, FBDD methods have been successfully applied to target the Ras/SOS complex [21,22] and the BRCA2/RAD51 complex [3].

Protein conformational changes upon ligand interaction make rational drug design even more complicated and challenging. Regarding fragment-like molecules, it is not fully accepted in the scientific community that such ligands can induce protein rearrangement, mostly because they bind proteins with very weak affinities [2]. However, as recently reviewed, resolution of 3D structures of fragment-protein complexes revealed that fragments could induce conformational change, even if they bind proteins with low affinity [23]. All these subtle protein conformational changes upon fragment binding were evidenced by X-ray

crystallography, through the comparison of the free protein and the complex structures [2,23–26]. X-Ray is clearly the method of choice for resolving structures, but sometimes it can be difficult to get crystals for protein-fragment complexes. Such structures can also be determined by NMR, using NOESY experiments, but the analysis is much longer and requires the full protein spectrum assignment. Here, we propose to use a very sensitive NMR parameter, the chemical shift, to compare the free and fragment-bound conformations of the protein. The analysis focuses on protein amine groups that can be rapidly assigned. Upon ligand recognition, proton chemical shifts of the protein are perturbed by the change in chemical environment due both to the presence of the ligand and to possible structural changes. The method described in this report relies on the fact that the large majority of fragments contain aromatic moieties. Aromatic rings are responsible for the so-called ring current shift effect [27], which constitutes the major contribution of the ligand-induced proton Chemical Shift Perturbations (CSP) in protein NMR spectra. The ring current shift caused by aromatic rings can be simulated by semi-classical equations, using the Haigh-Maillon model [27–30]. Thus, disagreement between experimental fragment-induced CSP and simulated fragment-induced CSP should highlight structural rearrangements of the protein upon interaction. Using 2D ^1H - ^{15}N protein spectra, protein residues located in regions that undergo conformational change upon fragment binding will be identified. To illustrate the method, we analyse the interaction of the Bcl-xL protein with a fragment that lead to the discovery of inhibitors ABT737 and ABT263, the most advanced fragment-based application of a PPI inhibitor [16,31,32].

Bcl-xL, as a member of the Bcl-2 family of proteins, is involved in the regulation of apoptosis. In normal cells, the anti-apoptotic proteins including Bcl-xL promote cell survival, while the pro-apoptotic members such as Bak and Bad promote cell death [33–35]. 3D structures of Bcl-xL bound to peptides from pro-apoptotic proteins showed that the protein undergoes rearrangement upon interaction, involving in particular the shift of the protein helix $\alpha 3$ [36–38]. Upon binding to PPI inhibitors, Bcl-xL structure is also modified, but the conformational change observed on helix $\alpha 3$ depends on the inhibitor size [16,39,40]. Regarding fragment-like ligands, Bcl-xL conformational change upon interaction has not been clearly investigated. Fragment-based NMR screening of 10^4 compounds performed against Bcl-xL identified fragment **1** (4'-fluoro-[1,1'-biphenyl]-4-carboxylic acid) as the best hit with a dissociation constant of 300 μM [15]. The structure of the protein-fragment complex has been calculated by docking the fragment into the protein structure using intermolecular protein-ligand NOEs obtained from ^{13}C , ^{15}N filtered NOESY experiments (PDB code 1YSG). During the calculation, the protein structure was kept rigid except for binding site residues [15], so the true structure of the protein-fragment complex has not been resolved. More recently, the group of Constantine applied the NOE matching approach to analyse the Bcl-xL/fragment **1** complex [41,42]. The authors used four different Bcl-xL structures, in the presence of Bak (1BXL), an NMR apo structure (1LXL), a X-Ray apo structure (1MAZ), and the fragment-bound structure 1YSG. The results suggested that the true fragment-bound structure might be more similar to the peptide-bound Bcl-xL structure (1BXL) than the 1YSG structure or the apo structures [42]. Here, to investigate Bcl-xL conformational change upon fragment binding, we compare fragment-induced experimental CSP with simulated CSP resulting from the ring current effect of fragment positions docked in the protein binding site. The analysis reveals that the protein undergoes structural rearrangements involving residues of helices $\alpha 2$, $\alpha 3$ and $\alpha 5$. To confirm the results and go further into

the characterisation of the fragment-induced conformational change, we performed Residual Dipolar Coupling (RDC) experiments, which are sensitive to the orientation of the backbone amine groups [43,44]. RDC have been previously used to explore protein conformational changes upon protein-protein interactions [45,46] and protein-ligand interactions [47,48]. RDCs were measured on the free and fragment-bound forms of Bcl-xL. The comparison of experimental RDCs and back-calculated RDCs on available protein structures confirms subtle Bcl-xL conformational changes upon fragment interaction. Thus, we propose to use proton CSPs as structural probes for investigating protein conformational changes upon fragment binding, and discuss the advantages and limits of the method.

Results

Experimental Bcl-xL Chemical Shift Perturbations upon binding to fragment 1

To investigate Bcl-xL conformational changes upon fragment binding, 2D NMR spectra were recorded for the protein in the absence and the presence of increasing concentrations of the compound **1** (Figure 1). Significant and linear shifts are observed for some of the ^1H - ^{15}N cross-peaks, while a large number of residue peaks display no perturbations, indicating a specific binding onto the binding site. Combined CSP including proton and nitrogen resonances ($\text{CSP}_{(H+N)}$) are mapped into the 3D structure of the free Bcl-xL protein in Figure 2 (see equation 3). The binding of fragment **1** induces large chemical shift perturbations for residues located in helices $\alpha 2$ (Gly94, Phe97, Glu98, Leu99, Tyr101 and Arg102), $\alpha 3$ (Asp107, Thr109 and Ser110) and $\alpha 5$ (Asn136, Trp137, Glu138, Arg139, Ile140 and Ala142). CSP are specifically observed for residues located into the groove of Bcl-xL that corresponds to the binding site of the apoptotic proteins [36–38]. More precisely, the fragment binding site corresponds to the Bcl-xL preferred hot spot of fragments, as previously demonstrated by fragment-based screening [15] and a NMR-based analysis of fragments resulting from deconstruction of Bcl-xL inhibitors [49]. Experimental proton CSP (CSP_H) values are displayed in red lines along the protein sequence in Figure 3.

Generation of Bcl-xL/1 complex structures for the calculation of fragment-induced CSP_H values

To compare experimental CSP_H values with fragment-induced simulated CSP_H values, 3D structures of Bcl-xL-fragment complexes are required. In the method we use here, the structure of the free protein should be available. To allow a large conformational sampling for the CSP simulation, 200 positions of fragment **1** were generated into the free structure of Bcl-xL binding site (1R2D) using AutoDock software [50]. As illustrated in Figure 4, five clusters are obtained with similar binding energies ranging from $-4.3 \text{ kcal.mol}^{-1}$ to $-5.7 \text{ kcal.mol}^{-1}$. Clearly, the binding mode of fragment **1** on Bcl-xL surface is driven by the interaction of the fragment carboxylate with the guanidinium of Bcl-xL arginine residues. Seventy-two out of the 200 positions interact with Arg132 (cluster **1**, red), 37 with Arg139 (cluster **2**, blue), 34 (cluster **3**, orange) and 43 (cluster **4**, purple) with Arg100, while 24 positions interact with Arg103 (cluster **5**, green). In fact, the docked positions in cluster **2** are very similar to the previously NOE-guided docked position of the fragment in the Bcl-xL/1 complex, as illustrated in Figure S1. In the published model (1YSG), fragment **1** interacts with Bcl-xL through an interaction with Arg139, which correlates with the observation that the modification of the carboxyl group position resulted in a dramatic decrease of affinity [15]. The hydrophobic biphenyl moiety is in




Figure 1. ^{15}N -HSQC spectra of the Bcl-xL protein in the presence of fragment 1. (A) Structure of fragment 1. (B) Superimposition of the ^{15}N -HSQC protein spectra in the free state (blue) and in the presence of increasing ligand concentration (200 μM in cyan, 300 μM in green, 500 μM in yellow, 700 μM in orange, 1 mM in red, 2 mM in pink and 4 mM in purple). (C) Section of the ^{15}N -HSQC spectrum. Numeration was done according to the PDB code 1R2D. doi:10.1371/journal.pone.0064400.g001

contact with residues Phe97, Tyr101, Ala104, Phe105, Leu130, Gly138, Arg139 and Ala142 (Figure S1).

Comparison of Experimental and Simulated CSP_H of Bcl-xL upon binding to fragment 1

GSP simulation for the 200 docked structures is shown in blue points in Figure 3. For each amide proton of Bcl-xL, the CSP_H value is simulated for the 200 ligand positions and compared to the experimental CSP_H observed for the same Bcl-xL amide proton. In addition, in supplementary material, results are displayed for the five clusters in distinct graphs (Figure S2). As illustrated on Figure 3, significant differences between experimental CSP_H values (red) and CSP_H values simulated for the 200 fragment positions (blue points) are observed.

In the approach we report here, we compare experimental CSP_H values with simulated CSP_H values. Cases where experimental CSP_H are larger than simulated CSP_H have to be distinguished from cases where the reverse is observed. Simulated CSP_H values can become very large when the amine proton is very close (in van der Waals interaction) to an aromatic proton of the ligand (Figure S3). This is the case for example in cluster 1 for residues Leu130 and Phe131 or in cluster 4 for residue Arg139 (Figure S2). Such results are obtained when the docking program places the ligand very close to the protein. Additionally, when saturation is not reached, maximal experimental CSP_H values can be limited by the dissociation constant of the complex, while simulated CSP_H values are calculated for a saturated binding site. Therefore, we focus here on residues for which experimental




Figure 2. Binding site of fragment 1 mapped onto the protein Bcl-xL surface. (A) The combined shift perturbations $\text{CSP}_{(H+N)}$ induced by fragment 1 mapped onto the protein surface. Residues that exhibit large perturbations are displayed in red ($\text{CSP}_{(H+N)} \geq 0.4 \text{ ppm}$) and orange ($0.4 > \text{CSP}_{(H+N)} \geq 0.15 \text{ ppm}$). (B) Ribbon structure of Bcl-xL in the free state (PDB code 1R2D) with the seven helices coloured sequentially. doi:10.1371/journal.pone.0064400.g002

CSP_H values are larger than simulated CSP_H values, as it is unexpected if no protein rearrangement occurs.

As shown in Figure 3, five amide protons located in helix $\alpha 2$ (Phe97 and Glu98), helix $\alpha 3$ (Thr109, Ser110) and helix $\alpha 5$ (Ala142) exhibit experimental CSP_H values much larger than the maximal simulated value ($|\text{experimental } \text{CSP}_H - \text{simulated } \text{CSP}_H| > 0.2 \text{ ppm}$). In addition, three residues of helix $\alpha 2$ (Ala93, Leu99 and Tyr101) as well as two residues of helix $\alpha 3$ (Asp107 and Ile114) exhibit differences larger than 0.06 ppm. When looking separately at each cluster, similar conclusion is drawn. For cluster 1, cluster 2 and cluster 4, experimental CSP_H values larger than simulated CSP_H values ($|\text{experimental } \text{CSP}_H - \text{simulated } \text{CSP}_H| > 0.2 \text{ ppm}$) are observed for residues 97, 98, 101, 102, 109, 110 and 142. For cluster 3, residues exhibiting large experimental CSP_H values are 97, 98, 101, 109, 110 and 142, and for cluster 5, residues are 97, 98, 109, 110 and 142. A P_{score} factor was calculated for all the 200 docked positions to estimate the disagreement between experimental and simulated CSP_H values (see equation 5). The P_{score} ranges from 0.0069 to 0.0165, and the average P_{score} values for the five clusters are similar (0.0087 for cluster 1, 0.0083 for cluster 2, 0.0093 for cluster 3,




Figure 3. Experimental versus simulated CSP_H values. Simulated CSP_H (blue points) are calculated for the 200 structures displayed in Figure 4. Experimental CSP_H values (red lines) are superimposed to the simulated CSP_H values. Residues 25 to 84 that are absent in the structure 1R2D are removed from the plot. doi:10.1371/journal.pone.0064400.g003




Figure 4. Docked positions of fragment 1 on the protein Bcl-xL binding surface. (A) Superposition of 200 structures of fragment **1** docked into the Bcl-xL binding site. Five clusters are observed (72 poses in red, 37 in blue, 24 in green, 24 in orange and 43 in magenta). (B) Energy binding (in kcal/mol) histogram for the 5 clusters. doi:10.1371/journal.pone.0064400.g004

0.0082 for cluster **4**, and 0.0092 for cluster **5**), indicating that none of the clusters exhibit a good agreement between experimental and simulated CSP_H values.

The residues for which experimental CSP_H values cannot be explained by the ring current shift of the ligand are mapped on the protein backbone in Figure 5A. The CSP_H analysis we report here clearly highlights structural rearrangement of Bcl-xL upon fragment binding, likely including backbone movement and side chain reorientation for residues located in helices $\alpha 2$ and $\alpha 3$. In addition, the experimental CSP_H value of residue Ala142 from helix $\alpha 5$ does not correlate with any simulated value. Ala142 is located in the Bcl-xL hot spot and very near from the residue Phe97. The latter might slightly move upon interacting with fragment **1**, inducing chemical shift perturbation for Ala142.

Residual dipolar coupling measurements for the free and fragment-bound forms of Bcl-xL

To confirm the conclusion resulting from the CSP_H analysis and validate the use of CSP_H as reliable probes for assessing protein conformational changes upon binding to fragment-like molecules, we also analysed Residual Dipolar Coupling (RDCs) for the free and fragment-bound forms of Bcl-xL. RDCs are a powerful source of long-range orientational information and are very sensitive to structural variations from known protein structures [43–45,47]. The RDC of a ^{15}N - ^1H pair value depends on the orientation of the N-H vectors with respect to the alignment tensor of the molecule and thus the direction of every ^{15}N - ^1H bond vector along the protein backbone would provide powerful assessment of the validity of any proposed structure. When 3D structures of proteins are available, RDCs can be back-calculated from the structure and compared with the measured RDCs [45,47]. Thus, it is possible to compare any form of a protein with a published structure. The correlation coefficient r between the experimental RDCs recorded in the absence of fragment and the




Figure 5. NMR evidences of Bcl-xL conformational change upon fragment binding. (A) CSP_H analysis. Significant differences between experimental and simulated CSP_H mapped onto the protein surface ($|CSP_H - CSP_H| \geq 0.06$ ppm). (B) RDC analysis. Residues with $|RDC_{exp} - RDC_{calc}| > 6.5$ Hz are displayed. doi:10.1371/journal.pone.0064400.g005

RDCs back-calculated from the free 1R2D Bcl-xL structure is 0.97 (Figure 6B). This indicates that 1R2D is a good model for the RDC analysis and that the solution structure in our experimental conditions is very similar to the published apo X-Ray structure 1R2D. The correlation slightly decreases to 0.92 when the back-calculated RDCs are compared to RDCs measured in the presence of the fragment. The outliers in the correlation plot correspond to residues of helix $\alpha 3$ (Ala104, Gln111 and His113) and helix $\alpha 5$ (Arg139 and Ala142) (Figure 6). Regarding helix $\alpha 5$, all residues but Arg139 and Ala142 exhibit a good correlation between experimental RDCs and back-calculated RDCs, suggesting that helix $\alpha 5$ does not move. Only the beginning of the helix, which is in direct contact with fragment **1**, is perturbed, in agreement with the CSP_H data. Regarding helix $\alpha 3$, three of the residues have a good correlation coefficient, three other residues could not be analysed due to spectral overlapping, and three residues located at both extremities of the helix (Ala104, Gln111 and His113) exhibit significant differences. The RDC measurements therefore confirm that a subtle conformational change upon binding to fragment **1** takes place in the binding region. The NH bonds of the residues with a bad correlation have a different orientation in the bound structure. The RDCs results are therefore in very good agreement with the CSP_H analysis (Figure 5B).

To go further into the analysis of the RDCs, we have focused the analysis on the $\alpha 2$ and $\alpha 3$ helices. Experimental RDCs are now compared to RDCs back-calculated using eight different Bcl-xL structures including apo (PDB codes 1R2D and 1LXL), ligand-bound (PDB codes 1YSG, 2O2M and 2YXJ) and peptide-bound (PDB codes 1G5J, 2PON and 1BXL) structures. The structures are described in Table 1 and compared in Figure 7. The correlation coefficient r between experimental and back-calculated RDCs ranges from 0.43 for 1G5J to 0.95 for 2O2M, and is 0.64 for 1R2D (Figure 8). The correlation is clearly better with ligand-bound structures (average $r = 0.85$) than with the free structures (average $r = 0.63$) or the peptide-bound structures (average $r = 0.45$). RDC measurements confirm that fragment **1** induces Bcl-xL adaptation upon interaction for residues located in helix $\alpha 3$ and the top of helix $\alpha 5$, and indicate that the rearrangement is more similar to the one observed in the presence of ligands such as in 2O2M than the one observed in the presence of peptide ligands.




Figure 6. Experimental versus back-calculated RDC on the free protein structure. (A) Comparison of the experimental RDC measured for the free protein and the calculated RDC using the free protein structure 1R2D. (B) Comparison of the experimental RDC measured in the presence of fragment **1** and the back-calculated RDC using the free protein structure 1R2D. Residues exhibiting $|RDC_{exp} - RDC_{calc}| > 6.5$ Hz are labelled. doi:10.1371/journal.pone.0064400.g006

Discussion

Recently, Surade and Blundell reviewed factors that make drug discovery difficult [2]. Among those factors, protein structural adaptation for efficient protein-ligand recognition was considered as a major problem in rational drug design. The authors recall that fragment-like molecules can induce conformational change but this is kinetically and thermodynamically less likely than for drug-like molecules. Protein conformational change can hamper the FBDD approach, since binding sites may be induced by the ligand, or protein conformers may be stabilised from an ensemble upon ligand recognition [2]. To date, few reports deal with fragment-induced protein conformational changes. Using X-ray crystallography, Babaoglu and Shoichet identified fragments that bound very weakly to the AmpC β -lactamase by inducing a novel binding site into the enzyme. The fact that crystallisation conditions were similar to those of the apo structure lead to the suggestion that the observed modification was not an artifact but a specific accommodation of these fragments [25]. Fragment-based screening of the HIV PR also identified fragment binding associated with conformational change in the protein [24]. Recently, a review by Murray and collaborators shows that out of 25 targets, 12 exhibited movement greater than 5 Å [23]. For example, in HSP90, some fragments induced the so-called collapsed helix formation around residue Gly108. For the well-known case of the BACE protein, fragments can induce significant conformational




Figure 7. PDB structures of Bcl-xL in free and complexed states. Helix $\alpha 3$ that moves upon ligand binding is coloured differently for the ligand-bound structures (1YSG, red; 2O2M, blue and 2YXJ, purple), for the peptide-bound structures (1G5J, cyan; 1BXL, yellow and 2PON, green), and for the free structure (1R2D, orange). doi:10.1371/journal.pone.0064400.g007

change in the Glycine-rich loop. Additional protein movement involving Asp168 swinging to form a hydrogen bond with the fragment OH group has also been observed [51]. All these reports were obtained from the resolution of the free and fragment-bound structures of the protein by X-Ray crystallography. Here, we demonstrate using NMR based on CSP and RDC measurements that Bcl-xL undergoes subtle local protein rearrangement upon fragment binding, involving residues of helices $\alpha 2$ and $\alpha 3$, and the very beginning of helix $\alpha 5$. This is an additional report showing that fragments can induce protein rearrangements upon interaction.

The RDC measurements show that Bcl-xL conformational change upon fragment binding is not as large as those induced by peptide ligands such as Bak, Bad or Beclin-1 [18,51,56] (Figure 8). This is not surprising since helix $\alpha 3$ shift upon peptide binding was shown to depend on the so-called position P1 of the peptide ligands [39]. This position is not occupied by fragment **1** which binds the protein hot spot [15,49]. In addition, ligands such as those in structures 2O2M and 2YXJ have different impact on Bcl-xL structures, showing that Bcl-xL clearly adapts its conformation to the ligand [16,40,52,53] (see Table 1 and Figure 7). Here we observe that a small ligand with 16 heavy atoms and a low affinity ($K_D = 300 \mu\text{M}$) induces Bcl-xL movement upon interaction, and this rearrangement is roughly similar to the one observed in a ligand-bound structure (2O2M), at least for the backbone conformation. In general, this raises the question of the intrinsic flexibility of proteins that accommodate various conformations depending on the ligands. For Bcl-xL, the backbone flexibility was recently characterised by MD simulations [52,53]. Starting from the structures bound to the Bad peptide, the structures did not reach the conformational space shown on the apo structures. Order parameters were compared for apo, holo without the peptide and holo with peptide structures. The region of helices $\alpha 2$ and $\alpha 3$ is flexible and the backbone flexibility is significantly reduced in the holo structure with peptide; for holo without peptide, higher degrees of flexibility in the loop $\alpha 2$ - $\alpha 3$ and $\alpha 3$ - $\alpha 4$ are observed when compared to the peptide-bound forms [53]. The higher degree of flexibility around helix $\alpha 3$ revealed in MD simulation correlates with the change of the length and conformation of helix $\alpha 3$ when binding to the peptide ligands, and correlates with the fragment-induced conformational changes revealed by our CSP and RDC analysis.

In the absence of protein conformational change, the main contributions to the ligand-induced chemical shift perturbations for proton CSP (CSP_H) are the ring-current effect of the ligand aromatic rings and the hydrogen bonds between the protein and




Figure 8. Experimental versus back-calculated RDC for helices $\alpha 2$ and $\alpha 3$. Comparison of the experimental RDC measured for the protein-fragment **1** complex and the back-calculated RDC on 8 different PDB structures: (A) 1R2D (B) 1LXL (C) 2O2M (D) 2YXJ (E) 1G5J (G) 2PON (H) 1BXL (See Table 1 for more details). doi:10.1371/journal.pone.0064400.g008

the ligand [30,54,55]. Nitrogen chemical shifts are more difficult to interpret and have not been used yet for analysing protein-ligand complexes. Fragment-like molecules represent simple organic compounds with few chemical functions and a very low molecular weight (<300 Da) that typically contain at least one aromatic ring. The ring current effect will therefore be largely predominant in the fragment-induced proton CSP_H . Hydrogen bond effects can be large, but this typically affects few protein residues, while ring-current effects are spread around the aromatic ring up, as illustrated in Figure S3. In addition, simulation of protein-ligand hydrogen bonds is still problematic [55–58]. Quantitative analysis of CSP_H for protein-ligand interactions has been reported for the first time by McCoy and Wyss in 2000 [30]. Ligand-induced CSP_H simulation has been used the last decade by three different groups for assessing ligand binding modes [55,59–61]. The CSP_H simulation consists of calculating the ring current effect on proton chemical shifts using the Haigh-Mallion model (equation 4). In the published reports, experimental CSP_H are compared to CSP_H simulated from docked ligand positions with semi-classical methods. The ligand binding mode corresponds to the ligand position exhibiting the best agreement between experimental and simulated CSP_H values. Published cases are the complexes formed between calmodulin and a naphthalene derivative using a Trp probe [30], HCV NS3 protease and a series of weak-affinity ligands [59], the protein antitumor antibiotic NSC and a synthetic chromophore analogue [60], barnase and deoxyoligonucleotides [61] and three kinase-ligand complexes [55]. In these examples where the ligand binding mode is deduced from the quantitative analysis of CSP_H , it is required that the protein does not undergo any conformational changes upon ligand binding. If the protein experiences a rearrangement upon interaction, experimental CSP_H will contain direct contributions from the ligand (ring current shifts) and indirect contributions due to protein conformational rearrangements such as backbone movements and side chain reorientations. For example, when rearrangement involves reorientation of aromatic residues, ring current effects of Phe, Tyr and Trp side chains will contribute to the CSP_H observed. For Bcl-xL, reorientation of aromatic side chains of residues Phe97, Tyr101 and Phe105 have been observed (Figure S4). The aromatic ring movements could contribute to the large CSP_H observed for residues in their vicinity. Finally, it is important to notice that RDC measurements on the free protein shows that 1R2D is a good starting structural model; therefore CSP disagreements do not result from divergences between the X-Ray Bcl-xL structure used for the docking and the structure in solution. In addition, RDC measurements complement CSP data as they show that the backbone of Bcl-xL is also modified in the helix $\alpha 3$ upon ligand interaction.

Here we do not solve the structure of the fragment-protein complex but we propose to use a fast NMR method to assess if an induced fit process is observed upon fragment binding. An assigned 2D NMR spectrum is necessary, which is easily feasible for proteins below 50 kDa. In addition, an apo 3D structure of the protein is required. When only a protein structure in a presence of a ligand is available, it is also possible to take the holo structure as the 3D model; disagreements will show that the protein coordinates have changed and that the holo and apo structure differ. For example, CSP_H values simulated with the ligand-bound

Table 1. Protein Bcl-xL available structures.

PDB Code	Structure determination	Ligand	ligand MW (g/mol)	Refs
1R2D	X-ray (resolution 1.95 Å)	none	none	[75]
1LXL	NMR (NOEs+hydrogen bonds+dihedral angle restraints)	none	none	[76]
1Y5G	NMR (docking+89 NOEs restraints)	4'-fluoro-1,1'-biphenyl-4-carboxylic acid	216	[15]
2O2M	NMR (docking+94 NOEs restraints)	4-(4-benzyl-4-methoxy-piperidin-1-yl)-N-[(4-[1,1-dimethyl-2-(phenylthio)ethyl]amino-3-nitrophenyl)sulfonyl]benzamide	688	[40]
2YXJ	X-ray (resolution 2.2 Å)	4-4-[(4'-chlorobiphenyl-2-yl)methyl]piperazin-1-yl-N-[4-((1R)-3-(dimethylamino)-1-[(phenylthio)methyl]propylamino)-3-nitrophenyl]sulfonamide	813	[16]
1BXL	NMR (138 NOEs+69 hydrogen bonds+71 ϕ torsional restraints)	BAK peptide (GNVGRNLAIGDDINR)	1697	[36]
2PON	NMR (NOEs+hydrogen bonds+dihedral angle restraints)	Bedin-1 peptide (GGTMENLSRRLKVTGDLFDIMSG)	2498	[39]
1G5J	NMR (121 NOEs+162 hydrogen bonds+192 ϕ and ψ torsional restraints)	BAD peptide (NLWAANRWGRELRMSDFEVDSEFKK)	3113	[37]

For the structure determination by NMR using docking (structures 1Y5G and 2O2M), the protein were held fixed with the exception of those residues involved in the binding groove (E96-L112, V127-A142, F191-L194). Peptide sequences are indicated in parenthesis. doi:10.1371/journal.pone.0064400.t001

2O2M Bcl-xL structure clearly highlight similar disagreements between experimental and simulated CSP_H values, with an average P_{score} value of 0.008 (Figure S5). Using the apo Bcl-xL structure or the holo 2O2M Bcl-xL structure, experimental CSP_H values for residues 97, 98, 101, 109, 110 and Ala142 are never explained by any ligand positions, showing that these residues are located in a region that moves upon ligand recognition. Disagreement between experimental and simulated CSPs larger than 0.2 ppm are observed for these residues. Previously published examples showed that in the absence of conformational change, we should not observe discrepancies between experimental and simulated CSP_H [30,60,61].

Conclusion

Protein-protein interfaces represent therapeutic targets for the future drugs. These interfaces are typically large and flexible, and as a consequence still remain a real challenge for drug discovery. Methods able to detect protein structural rearrangements upon interactions should therefore be useful in this context, to identify proteins subject to conformational change, to locate these changes, and to compare structural modifications with MD calculations. The results we report here demonstrate that CSP_H analysis could be routinely used for this purpose.

Materials and Methods

Proteins production and purification

The protein Bcl-xL was expressed as a 6His-tagged protein in *Escherichia coli* strain BL21(DE3 gold) using pQE-30 expression vector. *E. Coli* were grown at 37°C in M9 minimal medium supplemented with thiamine and containing $^{15}\text{N}_4\text{Cl}$ as the sole nitrogen source to produce uniformly ^{15}N -labelled protein. The protein expression was induced with isopropyl β -D-1-thiogalactopyranoside (0.5 mM) for 2 h. Cells were then lysed in 20 mM imidazole, 20 mM sodium phosphate, 500 mM NaCl supplemented by lysozyme and DNase (pH = 7.4) by sonification and clarified by centrifugation. The 6His-tagged protein contained in the supernatant was purified onto a His GraviTrap column (GE Healthcare) by Ni^{2+} -affinity chromatography. The protein was eluted with 500 mM imidazole, 20 mM sodium phosphate buffer and 500 mM NaCl. The protein buffer was then exchanged by dilution/concentration cycles, against 25 mM sodium phosphate, (pH = 7.0) containing 3 mM DTT (Dithiothreitol).

CSP measurements

NMR samples contained 200 μM uniformly ^{15}N -labelled Bcl-xL and ligand concentrations from 0 to 4 mM (saturation). The concentration of $\text{DMSO-}d_6$ did not exceed 3% in the NMR tube. 2D ^{15}N -HSQC spectra were acquired at 28°C with a Varian Inova 600 MHz NMR spectrometer, equipped with a standard 5 mm triple-resonance inverse probe with z-axis field gradient, using 64 t1 increments. Control 1D spectra preceded all experiments to assess the purity and stability of the fragment. All NMR spectra were processed with the Varian *Vnmj* and the *NMRPipe* softwares and analysed using *NMRView* and *Sparky* [62–64].

The proton and nitrogen chemical shift perturbations (CSP_H and CSP_N , respectively) induced by the fragment were defined as the difference between the chemical shift of the protein in the bound and the free states (see eq.1 and eq.2).

$$CSP_H = \delta^1 H_{bound} - \delta^1 H_{free} \quad (1)$$

$$CSP_N = \delta^{15}N_{bound} - \delta^{15}N_{free} \quad (2)$$

The combined perturbation $CSP_{(H+N)}$ was calculated using the proton (CSP_H) and the nitrogen (CSP_N) chemical shift perturbations [65]:

$$CSP_{(H+N)} = \sqrt{\frac{(CSP_H)^2 + \frac{(CSP_N)^2}{25}}{2}} \quad (3)$$

Docking calculation

The generation of 200 ligand poses located in the binding site was performed using AutoDock4 with the AutoDockTools4 graphical interface [50]. Grid maps were generated with 0.375 Å spacing into the protein binding site. The docking calculations were performed using Genetic Algorithm (GA) for ligand conformational searching. The 3D structure used was the apo X-ray structure 1R2D. The protein was kept rigid during the docking procedure.

CSP simulation

CSP_H were calculated by means of the Haigh-Maillon semi-classical model [27] (eq.4) widely used for CSP_H calculation on amide proton and in other popular programs (SHIFTX [28], SHIFTS [29], Shifty [66], CH3Shift [67] and SPARTA [68]):

$$CSP_H = fB \sum_{ij} S_{ij} \left(\frac{1}{r_i^3} + \frac{1}{r_j^3} \right) \quad (4)$$

Here, f is the ring-specific intensity factor (1.00 for benzene type ring), B is the target nucleus factor ($B = 7.06 \cdot 10^{-6}$ for amide nuclei [28]). Other values for f and B can be found in a recent work [69]. r_i and r_j are the distances from the ring atoms i and j to the proton HN of the protein. S_{ij} is the area of the triangle formed by atom i and j and the HN proton projected onto the plane of the aromatic ring. The sums are over the bonds in the ring.

We wrote a Fortran program to calculate the CSP_H induced by a fragment position on each protein amide proton. The program needs ligand PDB file (provide by docking experiments) and associated protein PDB file to load nucleus coordinates (available formats: .pdb and .pdbqt). To evaluate the agreement of the simulation with experimental CSP_H a factor P_{score} was introduced in the program and calculate for each pose (j):

$$P_{score}(j) = \frac{1}{N} \sum_i (CSP_{exp}(i) - CSP_{sim}(i))^2 \quad (5)$$

The number of protein residues was considered by N ($N = 196$ for Bcl-xL). Low P_{score} indicates that the docking solution is in good agreement with the experimental CSP. Nevertheless, the ligand-protein complex likely exists as energetically close-states, that are not necessarily discriminated by the CSP and the P_{score} values, especially since simulated CSP only contain ring-current shift contributions.

RDC

HN RDCs were measured in 25 mM sodium phosphate, 50 mM NaCl, 3 mM DTT at 28°C with IPAP-type experiment

[70] using 20 mg/mL of Pf1 LP11-92 phage. RDC experiments were performed for the protein Bcl-xL alone (350 μM) and in the presence of the fragment (2 mM). In the presence of anisotropic medium, the 2H signal splitting was 20 ± 5 Hz for the free and fragment-linked of Bcl-xL. This ensure that similar degree of alignment is used for both. 256 increments t1 were recorded in the indirect dimension ^{15}N and RDC values were obtained from the differences in the ^{15}N - 1H coupling observed in the isotropic and anisotropic case. RDCs ranged from -33 Hz to 29 Hz and from -33 Hz to 23 Hz for the protein in the free state and in the presence of the fragment **1** respectively. Residues showing overlapped signals were removed from the analysis that was performed with the in-house program ALTENS [71]. The RDCs were back-calculated as previously published [71], using data collected in both presence and absence of ligand according to the method of Singular Value Decomposition (SVD) [72]. To account for the goodness of the fit, correlation factors r (Pearson factor) and quality factors Q were calculated [73].

Supporting Information

Figure S1 Bcl-xL/fragment 1 complex. (A) Docked Bcl-xL-fragment complex that best mimics the complex structure available in the PDB (included in cluster **2**). (B) Bcl-xL-fragment **1** structure determined by Petros and coworkers (PDB code 1YSG). For both, hydrophobic residues are shown in yellow and residues labelled in bold are involved in hydrogen bond or electrostatic interaction (Ligplot+ analysis [74]). (TIF)

Figure S2 Experimental versus simulated CSP_H values. Experimental CSP_H values (red lines) are superimposed to the simulated CSP_H values calculated using the PDB file 1R2D (blue points). Comparison between experimental and calculated results are shown for (A) cluster **1**, (B) cluster **2**, (C) cluster **3**, (D) cluster **4** and, (E) cluster **5**. Residues 25 to 84 are removed from the plot. (TIF)

Figure S3 Iso-shielding curves of the ring current effect induced by a benzene ring on chemical shift amide proton. The chemical shift perturbations values calculated according to the Haigh-Maillon theory are labelled on each curve and expressed in ppm. Iso-shielding curves (A) in the benzene ring plane (B) in the plane perpendicular to the benzene ring plane. (TIF)

Figure S4 Aromatic rings located in helices $\alpha 2$ and $\alpha 3$ of Bcl-xL. Each structure is coloured by PDB code to compare the position of (A) Phe97, (B) Tyr101, and (C) Phe105. (TIF)

Figure S5 Experimental CSP_H values versus simulated CSP_H values calculated with the structure 2O2M. Simulated CSP_H (blue points) are calculated for the 200 structures using the PDB file 2O2M. Experimental CSP_H values (red lines) are superimposed to the simulated CSP_H values. Residues 25 to 84 are removed from the plot. (TIF)

Acknowledgments

The plasmid for the Bcl-xL protein was kindly provided by Prof. Mingjie Zhang (Hong Kong University of Science and Technology).

Author Contributions

Conceived and designed the experiments: IK. Performed the experiments: CA FG. Analyzed the data: CA TtB OW DD. Wrote the paper: IK.

References

- Braun P, Gingras AC (2012) History of protein-protein interactions: from egg-white to complex networks. *Proteomics* 12: 1478–1498.
- Surade S, Blundell TL (2012) Structural biology and drug discovery of difficult targets: the limits of ligandability. *Chem Biol* 19: 42–50.
- Scott DE, Ehebauer MT, Pukala T, Marsh M, Blundell TL, et al. (2013) Using a fragment-based approach to target protein-protein interactions. *Chembiochem* 14: 332–342.
- Morelli X, Bourgeois R, Roche P (2011) Chemical and structural lessons from recent successes in protein-protein interaction inhibition (2p2i). *Curr Opin Chem Biol* 15: 475–481.
- Sperandio O, Reyns CH, Camproux AC, Villoutreix BO (2010) Rationalizing the chemical space of protein-protein interaction inhibitors. *Drug Discov Today* 15: 220–229.
- Arkin MR, Randal M, DeLano WL, Hyde J, Luong TN, et al. (2003) Binding of small molecules to an adaptive protein-protein interface. *Proc Natl Acad Sci U S A* 100: 1603–1608.
- Bower JF, Pannifer A (2012) Using fragment-based technologies to target protein-protein interactions. *Curr Pharm Des* 18: 4685–4696.
- Molle IV, Thomann A, Buckley DL, So EC, Lang S, et al. (2012) Dissecting fragment-based lead discovery at the von hippel-lindau protein: hypoxia inducible factor 1 α protein-protein interface. *Chem Biol* 19: 1300–1312.
- Kuo LC (2011) Fragment-based drug design: tools, practical approaches, and examples. San Diego: Academic Press. 591 p.
- Shuker SB, Hajduk PJ, Meadows RP, Fesik SW (1996) Discovering high-affinity ligands for proteins: Sar by nmr. *Science* 274: 1531–1534.
- Hopkins AL, Groom CR, Alex A (2004) Ligand efficiency: a useful metric for lead selection. *Drug Discov Today* 9: 430–431.
- Bembenek SD, Tounge BA, Reynolds CH (2009) Ligand efficiency and fragment-based drug discovery. *Drug Discov Today* 14: 278–283.
- Carr RAE, Congreve M, Murray CW, Rees DC (2005) Fragment-based lead discovery: leads by design. *Drug Discov Today* 10: 987–992.
- Petros AM, Huith JR, Oost T, Park CM, Ding H, et al. (2010) Discovery of a potent and selective bcl-2 inhibitor using sar by nmr. *Bioorg Med Chem Lett* 20: 6587–6591.
- Petros AM, Dinges J, Augeri DJ, Baumeister SA, Betebenner DA, et al. (2006) Discovery of a potent inhibitor of the antiapoptotic protein bcl-xl from nmr and parallel synthesis. *J Med Chem* 49: 656–663.
- Lee EF, Czabotar PE, Smith BJ, Deshayes K, Zobel K, et al. (2007) Crystal structure of abt-737 complexed with bcl-xl: implications for selectivity of antagonists of the bcl-2 family. *Cell Death Differ* 14: 1711–1713.
- Friberg A, Vigil D, Zhao B, Daniels RN, Burke JP, et al. (2013) Discovery of potent myeloid cell leukemia 1 (mcl-1) inhibitors using fragment-based methods and structure-based design. *J Med Chem* 56: 15–30.
- Rega MF, Wu B, Wei J, Zhang Z, Cellitti JF, et al. (2011) Sar by interligand nuclear overhauser effects (iloes) based discovery of acylsulfonamide compounds active against bcl-x(l) and mcl-1. *J Med Chem* 54: 6000–6013.
- Braisted AC, Oslob JD, Delano WL, Hyde J, McDowell RS, et al. (2003) Discovery of a potent small molecule il-2 inhibitor through fragment assembly. *J Am Chem Soc* 125: 3714–3715.
- Tsao DHH, Sutherland AG, Jennings LD, Li Y, Rush TS, et al. (2006) Discovery of novel inhibitors of the zipa/ftsZ complex by nmr fragment screening coupled with structure-based design. *Bioorg Med Chem* 14: 7953–7961.
- Sun Q, Burke JP, Phan J, Burns MC, Olejniczak ET, et al. (2012) Discovery of small molecules that bind to k-ras and inhibit sos-mediated activation. *Angew Chem Int Ed Engl* 51: 6140–6143.
- Maurer T, Garrenton LS, Oh A, Pitts K, Anderson DJ, et al. (2012) Small-molecule ligands bind to a distinct pocket in ras and inhibit sos-mediated nucleotide exchange activity. *Proc Natl Acad Sci U S A* 109: 5299–5304.
- Murray CW, Verdonk ML, Rees DC (2012) Experiences in fragment-based drug discovery. *Trends Pharmacol Sci* 33: 224–232.
- Perryman AL, Zhang Q, Soutter HH, Rosenfeld R, McRee DE, et al. (2010) Fragment-based screen against hiv protease. *Chem Biol Drug Des* 75: 257–268.
- Babaoglu K, Shoichet BK (2006) Deconstructing fragment-based inhibitor discovery. *Nat Chem Biol* 2: 720–723.
- Carra JH, McHugh CA, Mulligan S, Machiesky LM, Soares AS, et al. (2007) Fragment-based identification of determinants of conformational and spectroscopic change at the ricin active site. *BMC Struct Biol* 7: 72.
- Haigh C, Mallion R (1979) Ring current theories in nuclear magnetic resonance. *Prog Nucl Magn Reson Spectrosc* 13: 303–344.
- Neal S, Nip AM, Zhang H, Wishart DS (2003) Rapid and accurate calculation of protein 1 h, 13c and 15n chemical shifts. *J Biomol NMR* 26: 215–240.
- Xu XP, Case DA (2001) Automated prediction of 15n, 13c α , 13c β and 13c' chemical shifts in proteins using a density functional database. *J Biomol NMR* 21: 321–333.
- McCoy MA, Wyss DF (2000) Alignment of weakly interacting molecules to protein surfaces using simulations of chemical shift perturbations. *J Biomol NMR* 18: 189–198.
- Oltersdorf T, Elmore SW, Shoemaker AR, Armstrong RC, Augeri DJ, et al. (2005) An inhibitor of bcl-2 family proteins induces regression of solid tumours. *Nature* 435: 677–681.
- Park CM, Bruncko M, Adickes J, Bauch J, Ding H, et al. (2008) Discovery of an orally bioavailable small molecule inhibitor of pro-survival b-cell lymphoma 2 proteins. *J Med Chem* 51: 6902–6915.
- Thomas S, Quinn BA, Das SK, Dash R, Emdad L, et al. (2013) Targeting the bcl-2 family for cancer therapy. *Expert Opin Ther Targets* 17: 61–75.
- van Delft MF, Huang DCS (2006) How the bcl-2 family of proteins interact to regulate apoptosis. *Cell Res* 16: 203–213.
- Youle RJ, Strasser A (2008) The bcl-2 protein family: opposing activities that mediate cell death. *Nat Rev Mol Cell Biol* 9: 47–59.
- Sattler M, Liang H, Nettlesheim D, Meadows RP, Harlan JE, et al. (1997) Structure of bcl-xl-bak peptide complex: recognition between regulators of apoptosis. *Science* 275: 983–986.
- Petros AM, Nettlesheim DG, Wang Y, Olejniczak ET, Meadows RP, et al. (2000) Rationale for bcl-xl/bad peptide complex formation from structure, mutagenesis, and biophysical studies. *Protein Sci* 9: 2528–2534.
- Liu X, Dai S, Zhu Y, Marrack P, Kappler JW (2003) The structure of a bcl-xl/bim fragment complex: implications for bim function. *Immunity* 19: 341–352.
- Feng W, Huang S, Wu H, Zhang M (2007) Molecular basis of bcl-xl's target recognition versatility revealed by the structure of bcl-xl in complex with the bh3 domain of beclin-1. *J Mol Biol* 372: 223–235.
- Bruncko M, Oost TK, Belli BA, Ding H, Joseph MK, et al. (2007) Studies leading to potent, dual inhibitors of bcl-2 and bcl-xl. *J Med Chem* 50: 641–662.
- Constantine KL, Davis ME, Metzler WJ, Mueller L, Claus BL (2006) Protein-ligand noe matching: a high-throughput method for binding pose evaluation that does not require protein nmr resonance assignments. *J Am Chem Soc* 128: 7252–7263.
- Metzler WJ, Caus BL, McDonnell PA, Johnson SR, Goldfarb V, et al. (2008) Application of protein-ligand NOE matching to the rapid evaluation of fragment binding poses. In: Zartler ER, Shapiro MJ, editors. *Fragment-Based Drug Discovery*. Chichester: John Wiley and sons. pp. 99–133.
- Tolman JR (2001) Dipolar couplings as a probe of molecular dynamics and structure in solution. *Curr Opin Struct Biol* 11: 532–539.
- Hu W, Wang L (2006) Residual dipolar couplings: Measurements and applications to biomolecular studies. In: Webb GA, editor. *Annual Reports on NMR Spectroscopy*, Academic Press, volume 58 of *Annual Reports on NMR Spectroscopy*. pp. 231–303.
- Hagn F, Klein C, Demmer O, Marchenko N, Vaseva A, et al. (2010) Bclxl changes conformation upon binding to wild-type but not mutant p53 dna binding domain. *J Biol Chem* 285: 3439–3450.
- Zhang D, Raasi S, Fushman D (2008) Affinity makes the difference: nonselective interaction of the uba domain of ubiquitin-1 with monomeric ubiquitin and polyubiquitin chains. *J Mol Biol* 377: 162–180.
- Umamoto K, Leffler H, Venot A, Valafar H, Prestegard JH (2003) Conformational differences in liganded and unliganded states of galectin-3. *Biochemistry* 42: 3688–3695.
- Tian F, Al-Hashimi HM, Craighead JL, Prestegard JH (2001) Conformational analysis of a flexible oligosaccharide using residual dipolar couplings. *J Am Chem Soc* 123: 485–492.
- Barelier S, Pons J, Marcillat O, Lancelin JM, Krimm I (2010) Fragment-based deconstruction of bcl-xl inhibitors. *J Med Chem* 53: 2577–2588.
- Morris GM, Huey R, Lindstrom W, Sanner MF, Belew RK, et al. (2009) Autodock4 and autodock-tools4: Automated docking with selective receptor flexibility. *J Comput Chem* 30: 2785–2791.
- Wang YS, Strickland C, Voigt JH, Kennedy ME, Beyer BM, et al. (2010) Application of fragment-based nmr screening, x-ray crystallography, structure-based design, and focused chemical library design to identify novel microm leads for the development of nm bace-1 (beta-site app cleaving enzyme 1) inhibitors. *J Med Chem* 53: 942–950.
- Novak W, Wang H, Krilov G (2009) Role of protein flexibility in the design of bcl-x(l) targeting agents: insight from molecular dynamics. *J Comput Aided Mol Des* 23: 49–61.
- Yang CY, Wang S (2012) Analysis of flexibility and hotspots in bcl-xl and mcl-1 proteins for the design of selective small-molecule inhibitors. *ACS Medicinal Chemistry Letters* 3: 308–312.
- McCoy MA, Wyss DF (2002) Spatial localization of ligand binding sites from electron current density surfaces calculated from nmr chemical shift perturbations. *J Am Chem Soc* 124: 11758–11763.
- Gonzalez-Ruiz D, Gohlke H (2009) Steering protein-ligand docking with quantitative nmr chemical shift perturbations. *J Chem Inf Model* 49: 2260–2271.
- Wishart DS, Case DA (2001) Use of chemical shifts in macromolecular structure determination. *Methods Enzymol* 338: 3–34.
- Parker LL, Houk AR, Jensen JH (2006) Cooperative hydrogen bonding effects are key determinants of backbone amide proton chemical shifts in proteins. *J Am Chem Soc* 128: 9863–9872.
- Moon S, Case DA (2007) A new model for chemical shifts of amide hydrogens in proteins. *J Biomol NMR* 38: 139–150.
- Wyss DF, Arasappan A, Senior MM, Wang YS, Beyer BM, et al. (2004) Non-peptidic small-molecule inhibitors of the single-chain hepatitis c virus ns3 protease/ns4a cofactor complex discovered by structure-based nmr screening. *J Med Chem* 47: 2486–2498.

60. Cioffi M, Hunter CA, Packer MJ, Spitaleri A (2008) Determination of protein-ligand binding modes using complexation-induced changes in (1)h nmr chemical shift. *J Med Chem* 51: 2512–2517.
61. Cioffi M, Hunter CA, Packer MJ, Pandya MJ, Williamson MP (2009) Use of quantitative (1)h nmr chemical shift changes for ligand docking into barnase. *J Biomol NMR* 43: 11–19.
62. Delaglio F, Grzesiek S, Vuister GW, Zhu G, Pfeifer J, et al. (1995) Nmrpipe: a multidimensional spectral processing system based on unix pipes. *J Biomol NMR* 6: 277–293.
63. Johnson BA, Blevins RA (1994) Nmr view: A computer program for the visualization and analysis of nmr data. *J Biomol NMR* 4: 603–614.
64. Goddard TD, Kneller DG (2004) Sparky 3. University of California, San Francisco, CA.
65. Schumann FH, Riepl H, Maurer T, Gronwald W, Neidig KP, et al. (2007) Combined chemical shift changes and amino acid specific chemical shift mapping of protein-protein interactions. *J Biomol NMR* 39: 275–289.
66. Hunter CA, Packer MJ (1999) Complexation-induced changes in 1 h nmr chemical shift for supramolecular structure determination. *Chem Eur J* 5: 1891–1897.
67. Sahakyan AB, Vranken WF, Cavalli A, Vendruscolo M (2011) Structure-based prediction of methyl chemical shifts in proteins. *J Biomol NMR* 50: 331–346.
68. Shen Y, Bax A (2007) Protein backbone chemical shifts predicted from searching a database for torsion angle and sequence homology. *J Biomol NMR* 38: 289–302.
69. Christensen AS, Sauer SPA, Jensen JH (2011) Definitive benchmark study of ring current effects on amide proton chemical shifts. *J Chem Theory Comput* 7: 2078–2084.
70. Ottiger M, Delaglio F, Bax A (1998) Measurement of j and dipolar couplings from simplified two-dimensional nmr spectra. *J Magn Reson* 131: 373–378.
71. Varadan R, Walker O, Pickart C, Fushman D (2002) Structural properties of polyubiquitin chains in solution. *J Mol Biol* 324: 637–647.
72. Losonczi JA, Andrec M, Fischer MW, Prestegard JH (1999) Order matrix analysis of residual dipolar couplings using singular value decomposition. *J Magn Reson* 138: 334–342.
73. Clore GM, Garrett DS (1999) R-factor, free r, and complete cross-validation for dipolar coupling refinement of nmr structures. *J Am Chem Soc* 121: 9008–9012.
74. Laskowski RA, Swindells MB (2011) Ligplot+: multiple ligand-protein interaction diagrams for drug discovery. *J Chem Inf Model* 51: 2778–2786.
75. Manion MK, O'Neill JW, Giedt CD, Kim KM, Zhang KYZ, et al. (2004) Bcl-xl mutations suppress cellular sensitivity to antimycin a. *J Biol Chem* 279: 2159–2165.
76. Muchmore SW, Sattler M, Liang H, Meadows RP, Harlan JE, et al. (1996) X-ray and nmr structure of human bcl-xl, an inhibitor of programmed cell death. *Nature* 381: 335–341.